

ADDENDUM # 2

Date: June 30, 2011

To: All Bidders (Maple Floor Replacement- Sportsplex)

From: Village of Orland Park

RE: INSTRUCTION TO BIDDERS Maple Floor Replacement - Sportsplex

This addendum becomes part of and modifies amends and clarifies the Bid Documents for the above mentioned project. All provisions and requirements of the Bid Documents shall remain in effect except as specifically changed below:

Please note that changes made concerning the Item Description. The following must apply:

Addendum # 2 – replaces Addendum #1 dated June 29, 2011 on its entirety.

PAGE 5

Part 2- Products

2.01 MATERIALS

A. Vapor Barrier

1. 6-mil polyethylene

~~a. Options~~

- ~~1) **Moisture Suppression System for projects with high concrete moisture.**~~

B. Subfloor

- a. Robbins 7/16" Zero/G™ shock pad.**
- b. Bio-Channel Star Subfloor panels that have been factory prepared to accept anchor channel.**
- c. 16 gauge metal Star Anchor Channels.**

C. Maple Flooring

- ~~1. 25/32" (20mm) thick x 2-1/4" (57mm) width, 2nd&Better grade, Unfinished TGEM, KD Northern Hard Maple, Continuous Strip® XL Flooring as manufactured by Robbins and graded in accordance with MFMA-FJ rules. ~~Flooring will have XL^{plus}™ technology to reduce or eliminate routine spacing for expansion.~~~~

~~a. Options~~

- 1) Thickness
 - a) 25/32" Thickness**
- 2) Face Width
 - a) 2 1/4" face width.**
- 3) Grade
 - a) 2nd & better grade**

b) MFMA-FJ flooring. Maple Flooring must be finger-jointed from manufacturer.

PAGE 6

4)Finish treatment

c) Factory-Sanded. (25/32" Flooring only)

D. Fasteners

1. Flooring – 1-1/4" (32mm) 18 gauge cleats or staples.
2. Subfloor
 - a. Channel anchors – Powers SPIKE® anchors.

PAGE 8

SPECIAL CONDITIONS:

- Floor must be striped and holes cut for existing equipment in floor now.
- Electric Piping into the floor with floor plates as per owner(owner will install)
- Stripe the gyms **with 5 Badminton and 3 Volleyball Courts**
- Add new logo as per owner
- Building will remain open at **all** times of construction.
- All construction debris material will be remove as per state and local laws
- Floor must be installed from August 20, 2011 to September 24, 2011
- Work hours Monday – Friday 7:00 am to 5:00 pm
- Any changes in floor heights from change in floor system basket heights and or door heights need adjustment and cost to be included in bid.**

Bidder's Signature: _____
Title

Company: _____

Date: _____

This document **MUST** be included in the bid package and acknowledgement must be indicated on the Bidder's Summary Sheet.